




MWMC: Built on Partnerships

MWMC Service Area

Westwater Treatment Plant

Eugene Springfield

MWMC Service Area

Miles

The Commission

<p>Pat Farr MWMC President Lane County Commission</p>	<p>Jennifer Yeh MWMC Vice-President Eugene City Council</p>
<p>Bill Inge Lane County citizen</p>	<p>Doug Keeler Springfield citizen</p>
<p>Walt Meyer Eugene citizen</p>	<p>Joe Pishioneri Springfield City Council</p>
<p>Peter Ruffier Eugene citizen</p>	

City of Springfield: *Administration*
City of Eugene: *Operations*
Lane County

3 elected officials
4 citizen representatives

MWMC: Regional Facilities

Wastewater Treatment Plant

- Plant operates 24/7, 365 days a year
- Capacity to handle peak flows of 277 million gallons/day

*Average flow
33 million gallons per day*



Photo: gpt/3

MWMC: Regional Facilities

Biosolids Management Facility

- Beneficial use of biosolids applied to agricultural land



Photo: gpt/4

Resiliency Project Purpose

- Establish resilient MWMC wastewater conveyance and treatment system that will effectively respond to meet community needs after a devastating natural disaster
 - Cascadia Subduction Zone Earthquake
 - 500 Year Flood
 - Climate Change Factored into Flood Assessment

Resilient ppt 05

Resilience Project Scope

- Setting of Service Goals for Recovery
- Vulnerability Assessment of MWMC Critical Infrastructure
- Critical Interdependencies Assessment
- MWMC Disaster Mitigation & Recovery Plan

Resilient ppt 06



LOS Goals – CSZ Seismic Event Conveyance Pump Stations & Pipelines - Consistent with Oregon Resilience Plan								
Phase 1: Short-Term			Phase 2: Intermediate-Term			Phase 3: Long-Term		
Days			Weeks			Months		
0-1	1-3	3-7	1-2	2-4	4-12	3-6	6-9	9-12
			Capable of routing 30% AWWF to Plant		Capable of routing 60% AWWF to Plant	Capable of routing 90% AWWF to Plant		
AWWF = Average Wet Weather Flow (52.5 million gallons per day)								


LOS Goals – CSZ Seismic Event Treatment Facilities

- Consistent with Oregon Resilience Plan

Target Timeframe for Recovery								
Phase 1: Short-Term			Phase 2: Intermediate-Term			Phase 3: Long-Term		
Days			Weeks			Months		
0-1	1-3	3-7	1-2	2-4	4-12	3-6	6-9	9-12
Flow to emergency outfall or through plant to regular outfall			Primary treatment and disinfection for ADWF			Primary treatment, secondary treatment, and disinfection for ADWF		Operating to meet regulatory requirements

ADWF = Average Dry Weather Flow (28 million gallons per day)

Performance Objectives for Structures – Seismic



Overall Findings of Geotechnical Evaluation:

- Geotechnical Conditions:
 - No significant areas of:
 - Liquefaction
 - Landslides or slip plane failures
 - Peak ground accelerations and velocities:
 - Considered to be moderate
 - Within design values for recent projects.
- Several locations along East Bank Interceptor identified for future site-specific analysis
- One area at the WPCF identified for analysis to better understand seismic-induced settlement/lateral spreading

Structural Observations – Pump Stations

- Irvington PS

Buried PS with no major structural deficiencies



Lateral Pipe Braces Needed



Anchors Needed to Attach Equip. to Base



Structural Observations – Pump Stations

- Glenwood PS

Overall only moderate upgrades identified.

Existing cracks should be analyzed to determine cause and then repaired.



Photo: gpt/13

Structural Observations – Pump Stations

- Wet Weather PS/Facility

Building will likely collapse due to “free story” type of failure mechanism; roof is not adequately attached to walls.



Photo: gpt/14

Structural Observations – Pump Stations

- Willakenzie PS



Overall only moderate upgrades identified for roof/wall connections

Cracks in older section of PS should be analyzed to determine cause and then repaired.

Electrical equipment should be assessed for seismic vulnerability – anchorage and bracing.




Structural Observations – Owosso Bridge



Force main

Power conduits




Beam-pier connection may fail causing failure of bridge

Example of Recommendations – Owosso Bridge

- Reinforcement of pier to beam interface at piers
- Geotechnical investigation at abutments to confirm no seismic-induced settlement or lateral spreading




Steel jacket



Performance Goals &
Seismic Vulnerability Assessment - Treatment


Phase 1 - Immediately after CSZ event (0 – 1 days)



Phase 2 – Intermediate-Term (1 to 2 Weeks)



Phase 3 – Long-Term (3 to 6 Months)



Typical Structural Deficiencies for Treatment Facilities

Structures Built in 1979

- Typical rigid wall / flexible diaphragm (RWFD) deficiencies.
- Roof to wall connections are not sufficient.
- Clear span construction will lead to failures.
- Can expect these buildings to be damaged and red-tagged after event if not upgraded.

Recent Structures

- Some items to be addressed but all in all will not be severely damaged after the event.

Tanks

- Good performance due to robust nature of design for leakage control and lack of significant ground movements.
- Wall added in aeration basin for process control was not designed for seismic loads and will likely fail.

Example of Recommendations - Treatment

Upgrade Rigid Wall Flexible Diaphragm Structures



Final Treatment Building



Primary Sludge PS



Boiler Building




Secondary Controls Building

Revised: 01/17/23

Example of Recommendations - Treatment

Operations Building – Upgrade for \$2.6 M or Replace?



- Reinforce roof system
- Reinforce roof to wall interface
- Reinforce wall to foundation
- Requires removal of all or parts of ceiling, roof, and interior walls to access
- Lateral bracing pipes/ducts, ceiling
- Equipment anchoring

Revised: 01/17/23

Typical Nonstructural Deficiencies for Collection System

1979 - 1990's Construction

- No Lateral bracing
- Fall-prone content like shelves and cabinets are not anchored.



Inadequate lateral bracing or anchoring


Recent Construction

- Bracing included.




Adequate lateral bracing

Eugene/Springfield Water Pollution Control Facility 500 Year Flood Elevation



Glenwood Pump Station 500 Year Flood Elevation



Critical Interdependencies Assessment

- Objectives:
 - Identify and understand top 10 dependencies that would substantially impact disaster response and recovery
 - Identify mitigation strategies to minimize potential for cascading failure



Top 10 Dependencies

Dependency	Rank
Employee and Family Preparedness	1
City/Regional Roads	2
Telecommunications	3
Structural Inspection	4
Emergency Operations Plan	5
Electrical Power	6
Data	7
Vendors and their Shipping Services	8
Fuel	9
Electrical, Piping, Equipment Assessments	10

Revised 10/1/13

Cost Summary

Estimated Capital Costs			
Facility	Seismic	Flooding	Total
Conveyance Pipelines	\$130,000	-----	\$130,000
Conveyance Pump Stations	\$5,155,000	\$900,000	\$6,055,000
WPCF	\$25,845,000	\$1,260,000	\$27,105,000
BMF	\$965,000	-----	\$965,000
Interdependencies	\$325,000		\$325,000
Totals	\$32,095,000	\$2,160,000	\$34,580,000

Estimated Annual O&M Cost	
Interdependencies: Emergency Preparedness, Communication Equipment, On-call Assessment & Vendor Contracts, and Staff Training	\$100,000

Revised 10/1/13

QUESTIONS?

Pharmacology ppt 01